



C-3

TRUCK
MOVEMENTS

DESIGNED BY: [Name]
 DRAWN BY: [Name]
 CHECKED BY: [Name]
 DATE: [Date]

PROJECT: 1414 Main Street Fire Station
 LOCATION: 1414 Main Street, Wentzville, MO
 SCALE: AS SHOWN

NOTES:
 1. ALL DIMENSIONS ARE IN FEET AND INCHES.
 2. ALL DISTANCES ARE TO CENTERLINE UNLESS OTHERWISE NOTED.
 3. ALL BEARINGS ARE TRUE BEARINGS.
 4. ALL CURVES ARE TO BE RADIUS UNLESS OTHERWISE NOTED.
 5. ALL UTILITIES SHOWN ARE BASED ON RECORD PLANS AND FIELD SURVEY.

PREPARED FOR:
 [Client Name]
 [Address]
 [City, State, Zip]

PREPARED BY:
 [Firm Name]
 [Address]
 [City, State, Zip]



A SET OF IMPROVEMENT PLANS FOR
FIRE HOUSE #1
 502 LUTKENHAUS BOULEVARD
 WENTZVILLE, MO 63385

PREPARED FOR:
 [Client Name]
 [Address]
 [City, State, Zip]

WENTZVILLE FIRE HOUSE #1 502 Luetkenhaus Blvd. Wentzville Mo. 63385

Additional concrete work RFP

November 6, 2018

PAGE 1

DEMOLITION			
DESCRIPTION	QUANTITY	UNIT COST	TOTAL
Mobilization	1 E.A.	\$	\$
Clearing/Grubbing	0.47 A.C.	\$	\$
Siltation (12" Silt Soxx)	562 L.F.	\$	\$
Stockpile 6" Topsoil	383 C.Y.	\$	\$
Removal of Pavers	Lump Sum	\$	\$
SUB TOTAL			\$

GRADING			
DESCRIPTION	QUANTITY	UNIT COST	TOTAL
Site Grading _Onsite Movement	1,870 C.Y.	\$	\$
Import Earthwork	1,567 C.Y.	\$	\$
Erosion Matting on 2:1 Slope	561 S.Y.	\$	\$
SUB TOTAL			\$

PAVEMENT			
DESCRIPTION	QUANTITY	UNIT COST	TOTAL
Subgrade Preparation	983 S.Y.	\$	\$
6" Mountable Curb	520 L.F.	\$	\$
8" Conc w/mesh. w/4" Rock	977 S.Y.	\$	\$
4" Conc. w/4" Equip Ramp/patio	122 S.Y.	\$	\$
Pavement Markings	LUMP SUM	\$	\$
Sub Total			\$

STORM SEWERS			
DESCRIPTION	QUANTITY	UNIT COST	TOTAL
12" Nyloplast Drain x 4" outlet	1 EA.	\$	\$
4" Insert tee w/hole saw	1 EA.	\$	\$
4" PVC Riser pipe (5' stick min sold)	1 EA.	\$	\$
Sub Total			\$

LANDSCAPING			
DESCRIPTION	QUANTITY	UNIT COST	TOTAL
Seeding	1,223 S.Y.	\$	\$
SUB TOTAL			\$

MISCELLANEOUS			
DESCRIPTION	QUANTITY	UNIT COST	TOTAL
Handrailing on Equip Ramp	2 EA.	\$	\$
Sub Total			\$

SUB TOTAL \$